








SW MANHOLE SCHEDULE

Manhole Number		Cover Level	Connections	Pipe			Manhole Size	Types		
Coordinates		Depth To Soffit		Code	Inverts	Diams		Manhole	Cover	
S1		8.500		1	PPS2-S1	7.150	150	450	Type D	450 x 450 D400
E.	91431.678	1.200		0	S1.001	7.150	150			
N.	10419.695									
S2		7.630		1	PPS1-S2	6.630	150	450	Type D	450 x 450 D400
E.	91469.042	0.850		0	S2.0001	6.630	150			
N.	10421.475									
S3		7.800		1	S1.001	6.580	150	450	Type D	450 x 450 D400
				2	S2.001	6.580	150			
E.	91458.127	1.070								
N.	10421.286			0	S1.001	6.580	150			
S4		6.500		1	S1.002	5.630	150	Temporary Bagwork Headwall		
E.	91457.065	0.720								
N.	10436.894									

FW MANHOLE SCHEDULE

Manhole Number		Cover Level	Connections	Pipe			Manhole Size	Types		
Coordinates		Depth To Soffit		Code	Inverts	Diams		Manhole	Cover	
F5		7.380		1	F1.004	4.630	450	Type D	450 x 450 B125	
E. 91473.541		2.650		2	Spur	4.630				100
N. 10426.529				0	F1.005	4.630				100
F6		7.520		1	F1.005	4.560	450	Type D	450 x 450 D400	
E. 91472.575		2.860								
N. 10420.830				0	F1.006	4.560				100
F7		8.800		1	F1.006	4.170	1200	Type A	600 X 600 D400	
E. 91441.740		4.530								
N. 10417.246				X	Capped Spur	4.170				100
				0	F1.007	4.170				100

Notes

- Do not scale from this drawing on print or electronically. Work from figured dimensions only.
- No deviation from the details on this drawing is allowed without CampbellReith's prior permission in writing.
- Read this drawing with all Architect's, Service Engineer's and CampbellReith's relevant details, specifications and drawings.
- All work is to be done in accordance with the relevant specifications issued by CampbellReith, British Standard Codes of Practice, Statutory Requirements and the Contract Documents.
- Drawing revision:
P: Preliminary Evolving drawings for approvals, tenders, billings etc.
C: Contractual Drawings authorized and approved for stage completion.
- Drawing status:
Work in progress
S0 - Initial status
Shared (Non-contractual)
S1 - Suitable for coordination, **S2** - Suitable for information, **S3** - Suitable for review and comment, **S4** - Suitable for stage approval.
Published (For contractors purposes)
A1, An etc - Authorised and accepted ('n' relates to work stages)
B1, Bn etc - Partial sign-off (with comments)
CR - As constructed record document (Final Construction ONLY. Any deviations to that which is on site is not the liability of CampbellReith)
- Work Stages:
2 - Concept, **3** - Definition, **4** - Design, **5** - Build & commission, **6** - Handover
- Only drawings with **revision Cn** and **status A5** to be used for **Construction**.
- Alternative proposals for "Perfect Manhole" to be reviewed by Civil Engineer

P1	Issued for Tender	19.11.25	NB
Rev	Description	Date	By

CampbellReith

consulting engineers

London

020 7340 1700

☐

Bristol

0117 916 1066

☒

Manchester

☐

Birmingham

☐

0161 819 3060

01675 467 484

www.campbellreith.com

Job Title

Ennor Farm

Client

The Council of the Isles of Scilly

Phase 1

Southern Access

Proposed Manhole Schedules

Drawn by	Date made	Scale @ A2	Checked by	Suitability	CR Project
NB	18.11.25	NTS	LM	S2	13847

Project No	Orig.	Funct.	Spatial	Form	Disc.	Number	Rev
13847	CRH	P1	SA	DR	C	5051	P1