NEC3 engineering and construction contract (ECC) Works Information

Project / Contract information

Project Name	Isles of Scilly Dune & Flood Defence Scheme- Porthloo
Project Reference	CloS to advise
Contract Reference	CloS to advise
Date	22 February 2021
Version Number	F1
Author	Maximillian Clausen / Stephen Swabey

Revision history

Revision date	Summary of changes	Version number
15-04-2019	Draft Issue	P1
22-02-2021	Final Issue	F1



Part 2: Non-returnable Documents
NEC - ECC 3rd Ed.

Works Information

Contents List

WI 100 Description of the works

WI 200 General constraints on how the Contractor provides the works

WI 300 Contractor's design

WI 400 Completion

WI 500 Programme

WI 600 Quality Assurance

WI 700 Tests and inspections

WI 800 Management of the works

WI 900 Working with the Employer and Others

WI 1000 Services and other things to be provided

WI 1100 Health and safety

WI 1200 Subcontracting

WI 1300 Title

WI 1400 Acceptance or procurement procedure (Options C and E)

WI 1500 Accounts and records (Options C and E)

WI 1600 Parent Company Guarantee (Option X4)

WI 1700 Performance Bond (Option X13)

WI 1800 Advanced payment bond (Option X14)

WI 1900 Low Performance damages (Option X17)

WI 2000 Employer's work specifications and drawings

APPENDIX A: EMPLOYER'S MINIMUM TECHNICAL REQUIREMENTS:

EA MTR

APPENDIX B: REVETMENT SPECIFICATION

Definitions List

Term	Description
CESWI	Civil Engineering Specification for the Water Industry, 7th Edition
EA MTR	Environment Agency Minimum Technical Requirements
SHW	Specification for Highway Works

Preamble

This Works Information describes and specifies the *works*. For details of the technical standards and the list of drawings used see **WI 2000**, *Employer's* work specification.



WI 100 Description of the works

WI 101 Project objectives

1. The project objectives are:

To protect Porthloo lane from erosion and undermining and to reduce the risk of overtopping and coastal flooding to the domestic and commercial properties located behind the beach. The scheme also aims to decrease the vulnerability of Lower Moors SSSI to saline intrusion during storm events.

The works involve construction of a concrete retaining wall faced with wood to continue the existing wooden retaining wall and placement of a rock armour revetment on the beach side of the retaining wall. Partial deconstruction of existing works will be required to construct the revetment.

WI 102 Rock Armour Revetment

- The rocks used in the construction of the revetment shall be similar to the natural granite bedrock found on the islands. For avoidance of doubt, this means that Cornish granite would be acceptable, but Norwegian granite would not be acceptable. The supervisor and/or Project Director will be the ultimate arbiter of what rock is acceptable.
- 2. The rocks used in the construction of the revetment shall be handled and placed in accordance with the requirements of the Revetment Specification. See Appendix B: UA008878-ARC-XX-XX-SP-CE-0831-P1.
- The plan of the rock armour revetment is contained in UA008878-ARC-XX-XX-DR-CE-0220-P4, while cross sections through the revetment are contained in UA008878-ARC-XX-XX-DR-CE-0221-P5, UA008878-ARC-XX-XX-DR-CE-0222-P5 and UA008878-ARC-XX-XX-DR-CE-0223-P5.
- 4. Setting Out Points (SoP) correspond to the rear of the crest and the intersection between the revetment face and the toe.
- 5. The revetment shall be underlain with a geotextile, ensuring it meets the properties stated in the Rock Specification (see Appendix B).
- 6. Where the geotextile is wrapped around the foremost rock of the toe, it shall be lapped back by a minimum of 2000mm and trapped in place by the rocks which form the toe.
- 7. The crest & toe top level width shall be 5 x D_{n50} (median nominal rock diameter) or 4500mm whichever is greater.
- 8. The revetment armour layer thickness, including the crest and toe, shall be a minimum of 2000mm.
- 9. Revetment slope grade shall vary and smoothly transition along its length from 1 in 3 at the at the extremities of the roundheads to 1 in 1:5 at its centre.

WI 103 Roundheads

- 1. The northern roundhead shall butt-up against the cliff face with the top toe level being 4.50mAOD and the top crest level being 7.60m AOD.
- 2. The southern roundhead shall be built into the existing the engineered defence and shall not butt-up against the existing vertical timber wall which retains the sand backfill for the existing defence. Rather, the rocks shall be placed so they are self-supporting within the revetment ensuring they meet the stability requirements stated in UA008878-ARC-XX-XX-SP-CE-0831-P1 (Appendix B). The roundhead crest and toe levels shall be the same the northern roundhead.

WI 104 Existing Engineered Dune

- 1. The existing defence is believed to comprise vertical timber sleepers (~1.6m above EGL), braced by a horizontal whaling beam at its rear. It has a sloped front face and level top surface covered by a geotextile planted with marram grass and backfilled with sand.
- 2. The existing engineered dune defence shall be excavated to accommodate the new southern roundhead. It is likely the timber wall foundations will become exposed during the excavation and the *Contractor* will ensure its continued stability.
- 3. Once the rock roundhead has been constructed, the void between the sloped revetment face and the existing cut-back engineered dune shall be backfilled with the site won rock to the pre-construction levels of the existing engineered dune.
- 4. The site-won rock is assumed to be the existing rock forming the existing ad-hoc revetment where the proposed revetment shall be built.
- The site won rock shall be that which is currently being used on the embankment as an adhoc revetment i.e. Cornish granite of the same colour and type that naturally occurs on the islands. See Site Information (UA008878-ARC-XX-XX-SP-CE-0801-P1), 3. Site Photos for an illustration.

WI 105 Retaining Wall

- 1. A retaining wall shall be constructed at the rear of the revetment to interface with the existing timber retaining wall. The proposed wall shall have the same finished height as the existing timber wall of 6.75m AOD and shall continue along the same alignment.
- L-shaped precast units shall form the retaining wall (UA008878-ARC-XX-XX-DR-CE-0230-P1) and shall be founded on a mass concrete foundation pad. The concrete shall be GEN3 as a minimum with reinforcing as designated in UA008878-ARC-XX-XX-DR-CE-0231-P1 and specified in PorthlooBBS231-P1.
- 3. The precast units shall be faced with Greenheart timbers to give the same aesthetic as the existing timber retaining wall. The timbers shall be of the same thickness, width and have the same finish height as the existing timber retaining wall. The finished timbers shall align with the existing timbers on the face away from the beach, so that the timber surface is not interrupted by a 'step' in the face. The timbers shall be bolted to precast units with stainless-steel fixings.

WI 107 Concrete

1. See BS 8500-1: 2015+A1:2016 designated concrete mix details. A summary of the details is as follows:

Table A.15 Summary of requirements for designated concretes^{A)}

Concrete designation	Min. strength class	De- fault slump class	Max. w/c ratio	Min. cement or combination content (kg/m³) for 20 mm max. aggregate size	Cement and combination types
GEN0	C6/8	S 3	_	120	CEM I, IIA, IIB-S, IIB-V, IIIA, IVB-V
GEN1	C8/10	S 3	_	180	CEM I, IIA, IIB-S, IIB-V, IIIA, IVB-V
GEN2	C12/15	S 3	_	200	CEM I, IIA, IIB-S, IIB-V, IIIA, IVB-V
GEN3	C16/20	S 3	_	220	CEM I, IIA, IIB-S, IIB-V, IIIA, IVB-V
RC20/25	C20/25	S 3	0.70	240	CEM I, IIA, IIB-S, IIB-V, IIIA, IVB-V
RC25/30	C25/30	S 3	0.65	260	CEM I, IIA, IIB-S, IIB-V, IIIA, IVB-V B)
RC28/35	C28/35	S 3	0.60	280	CEM I, IIA, IIB-S, IIB-V, IIIA, IVB-V B)
RC30/37	C30/37	S 3	0.55	300	CEM I, IIA, IIB-S, IIB-V, IIIA, IVB-V B)



WI 200 General constraints on how the Contractor provides the works

WI 201 General constraints

- 1. The *Contractor* shall comply with the following constraints in addition to those identified in the CESWI & EA Minimum Technical Requirements.
- 2. The *Contractor* shall comply with the constraints and measures identified in the Construction Environment Management Plan (CEMP)

WI 202 Site Access

1. Access to site is via Porthloo lane. This road shall remain open to traffic during the works.

WI 203 Working Area

- The Contractor's working area is indicated on drawing UA008878-ARC-XX-XX-DR-CE-0220-P4
- 2. If the Contractor wishes to modify these areas, he shall obtain written permission from the *Project Manager*.

WI 204 Parking

1. The *Contractor* shall provide adequate parking for site-based personnel and visitors within the working area. No parking is allowed outside of this area, unless permission is obtained from the *Project Manager*.

WI 205 Working Hours

1. No additional constraints to 1.27 EA MTR and in terms of local limits on working hours.

WI 206 Operational constraints

- 1. Porthloo lane shall remain open to vehicular traffic for the duration of the contact.
- 2. The residential properties located behind the beach shall have unhindered pedestrian and vehicular access to and from their properties.
- 3. The commercial boat yard, to the south of the revetment, shall not have its operational activities hinder by the *works*.
- 4. Sections of the work along the foreshore are at risk of being cut off by the incoming tide and are exposed to wave action. The contractor will be required to plan works around tide times and to monitor weather forecasts/conditions to make sure that the risk to staff and machinery is kept to a minimum managed in accordance with the latest H&S legislation.

WI 208 Existing services

- All known services information is included within the Site Information. Prior to carrying out the
 works the *Contractor* shall independently verify the location of all known services, and
 actively search for any previously unidentified services prior to carrying out any intrusive
 ground works.
- 2. The *Contractor* shall undertake all discussions with Utility Companies to gain the required permissions for the works on or around services.

WI 209 Ground conditions

1. A ground investigation was undertaken on the 17th May 2017 to determine the level of the periglacial clay deposits, colloquial known as Ram, which underlie the beach material. See UA008878-ARC-XX-XX-SP-CE-0801-P1, Appendix C, for trial pit logs.

WI 210 Permanent Access

- 1. A footpath is illustrated on the 1:25,000 O.S. map behind the existing engineered dune. Where the working area blocks the route, the path shall be diverted temporarily along the boat yard boundary fence during construction works. The temporary path shall have a minimum width of 1.5m.
- 2. The original path shall be reinstated when the construction works are completed.
- 3. Signs shall be placed at each end of the footpath where it is diverted, to advise the public of the diversion and the reason for the diversion

WI 211 Storage of fuel and chemicals

1. No additional constraints to those identified in the MTR

WI 212 Pollution, ecological and environmental impacts

- 1. Debris burning shall not be permitted under any circumstances.
- Works shall follow best practice guidance for pollution control. All materials, including
 machinery, shall be securely stored in the site compound when not in use. Staff shall be
 appropriately trained on how to use spill kits correctly. Small plant (including generators)
 shall be placed within drip-trays or plant nappies.
- 3. Detailed construction method statements will be prepared following Institute of Air Quality Management (IAQM) guidelines on dust management for medium risk-sites.
- 4. Out of hours works will be avoided wherever reasonably practicable.
- 5. Noise impacts will be minimised by adherence to measures described in BS 5228, to reduce noise impacts from construction by 5dB to 15dB.
- 6. Detailed construction method statements will be prepared following Institute of Lighting Practitioners guidance.
- Waste that is recyclable will be sorted within the construction compound, placed into the
 relevant storage disposal container, and then removed from site for disposal at an
 appropriate recycling facility.
- 8. All potentially contaminated material will be subject to Waste Acceptance Criteria testing.
- 9. Any excavated clay that cannot be reused would be bulked on site and disposed of at an appropriately licenced waste management facility.
- 10. All residual waste material will be removed from site and disposed of at an appropriately licenced waste management facility.
- 11. Detailed construction method statements will be prepared following CIRIA guidance to include:
 - a. Site storage of fuel and any chemicals on site will be above Mean High Water Spring and away from high-risk locations.
 - b. All chemicals of a hazardous nature will be stored in bunded, locked containers in surfaced areas (bund to contain 110% of the capacity of the liquid stored).
 - c. Plant, equipment and vehicle refuelling will only be permitted at designated refuelling areas.
 - d. Refuelling and bulk deliveries will be supervised.

- e. Emergency spill kits will be available at all times and operatives should be trained in their use. Any spillages would be contained and reported.
- f. Drip trays will be used to prevent oil leaking from machinery when parked or stored and during refuelling.

WI 213 Archaeological requirements

1. There are no know areas of interest which interface with the works area and/or require further investigation.

WI 214 Confidentiality

- 1. The *Contractor* shall not disclose information regarding the works to third parties without the acceptance of the *Project Manager*.
- 2. All contact from third parties will be forwarded to the *Project Manager*.
- 3. The Contractor may publicise the services only with the Employer's written permission.

WI 215 Security and protection on the site

- 1. The *Contractor* is responsible for the security of the site and for vehicles and pedestrians entering and leaving the site.
- 2. Security measures shall include ensuring that the *Contractor's* personnel are easily identifiable.

WI 216 Protection of existing structures and services

- The existing engineered dune defence shall be excavated at its northern most extent to
 accommodate the southern revetment roundhead. The excavation shall ensure the timber
 sleeper wall which forms the rear extent of the exiting engineered dune, remains supported
 and intact during the works, or if it is removed to aid construction, it is to be reinstalled to its
 original line, level and condition.
- 2. An existing sewer outfall for a septic tank is shown on the contract drawings. It is reported as not being live. This shall be removed if necessary.

WI 217 Protection of the works

1. The *Contractor* should state in the Method Statement any measures they will employ to protect the works in the temporary state during periods of unsettled sea states. See Appendix B for details on how the revetment works should be protected during construction.

WI 218 Cleanliness of the roads

1. No additional constraints to those identified in the MTR.

WI 219 Traffic Management

- The Contractor is responsible for traffic safety and management including obtaining all approvals, e.g. road closures and openings. Before any work in, or affecting the use of, any highway or road is commenced, the Contractor's proposed method of working, including any special traffic requirements, is agreed with and confirmed in writing to, the Project Manager, and all relevant authorities.
- 2. The *Contractor* shall produce a Traffic Management Plan to be submitted to the *Project Manager* prior to construction of the works.

- 3. The Traffic Management Plan is to include, but is not limited to, the following:
 - Access routes to be taken by heavy vehicles, noting any height or weight restrictions
 - · Details for keeping roads clear of dust and mud
 - Timings for heavy load movements
 - Vehicular routing
 - Parking restrictions for construction vehicles on the public highway surrounding the site
 - Pedestrian walkways around the site
 - Storage areas
 - Timetable for removal of site compound equipment
- 4. The *Contractor* co-operates with the relevant authorities concerning works in, or access to, the highway. The *Contractor* informs the *Project Manager* of any requirements or arrangements made with the relevant authorities.
- 5. The *Contractor* shall be responsible for liaising with the public regarding road closures and regular movements on the highway.

WI 220 Condition survey

- 1. At least two weeks prior to taking possession of the Site, the *Contractor* shall undertake condition surveys in accordance with the *Employer's* Minimal Technical Requirements.
- 2. The *Contractor* shall make a note of any existing damage and bring this to the attention of the *Project Manager*.
- 3. The *Contractor* shall repeat the condition survey on completion of the works in accordance with the *Employers* Minimum Technical Requirements and provide a copy to the *Project Manager*.
- 4. Photographs, surveys and inventories must be date stamped, NRG referenced, and copies held by the *Contractor*. The *Contractor* shall provide these to the *Project Manager* and the *Supervisor*.
- 5. The Contractor shall undertake condition surveys with the Supervisor, and any others invited by the Contractor, Project Manager or Supervisor. The Contractor, Project Manager and Supervisor notify each other in advance if any others are invited.
- 6. The *Contractor* is to give at least one weeks' notice to the *Project Manager* and *Supervisor* prior to undertaking any condition survey.
- 7. All record photographs and videos shall comply with the requirements of the Minimum Technical Requirements.

WI 221 Consideration of Others

1. No additional constraints to those identified in the MTR.

WI 222 Control of site personnel

1. The *Contractor* shall ensure that all persons working on or visiting the Site hold a valid and current Construction Skills Certification Scheme (CSCS) card. A member of the site team shall escort persons without this card at all times.

 The Contractor will maintain a visitors' book recording the date, the time in, the time out, evidence of a specific Health and Safety induction, CSCS number, and the name and company of the person visiting.

WI 223 Site cleanliness

1. No additional constraints to those identified in the MTR.

WI 224 Waste materials

- Any construction related materials shall be disposed of away from site without any contamination of the waterways or surrounding land. Disposal must be in accordance with a Site Waste Management Plan (SWMP) produced by the *Contractor* and by a licensed waste disposal *contractor* with an audit trail. Refer to 1.14 EA MTR.
- 2. The *Contractor* shall determine volumes of waste to be disposed of offsite and apply for the appropriate licences
- 3. The SWMP shall be submitted to the Project Manager for acceptance prior to works on site commencing.

WI 225 Deleterious and hazardous materials

1. No additional constraints to those identified in the MTR.

WI 226 Consents & Licencing

1. A Marine Management Organisation (MMO) Licence is required for the proposed works. Work is not to commence on site prior to the MMO licence being in place. See **WI 1002**.

WI 227 Excavating Material

- 1. Excavated material is to be placed in an area agreed with the Project Manager.
- 2. The *Contractor* is responsible for removing any excavated material from the site which cannot be redistributed within the working area.
- 3. The *Contractor* is responsible for all, permits, permissions and costs associated with removal and disposal of surplus material.

WI 228 Reinstatement

- 1. The works area, in particular the grassed compounded areas, adjacent to the boat yard shall be reinstated in their preconstruction condition.
- 2. The *Contractor* shall seed any bare soil patches within the works area behind the revetment using Mixture 4, CESWI 2.56, point 1.

WI 300 Contractor's design

WI 301 Design responsibility

1. The Contractor is not required to design any elements of the scheme.

WI 400 Completion

WI 401 Completion definition

- 1. The following are absolute requirement for Completion to be certified, without these items, the *Employer* is unable to use the works:
 - The whole of the works has been completed in accordance with the Works Information.
 - There are no Defects that prevent safe access and operation by the Employer.
 - There are no Defects that present a health and safety hazard to the public or landowners.
 - 1 paper copy and 1 electronic copy of the final Health and Safety File.
 - 1 hard copy of As Built drawings and one electronic version

WI 402 Access to information following Completion

- 1. The *Contractor* shall provide all information relevant to the works to the *Project Manager* following completion. The *Contractor* shall retain copies of all information for inspection by the *Project Manager* for the duration of the contract liability period.
- 2. The *Contractor* shall retain a copy of all design records, software code, supplier's details and other relevant information for a period of at least 12 years following Completion and shall make these available to the *Employer* on request.

WI 403 Final Clean

1. The *Contractor* shall leave the site in a clean, tidy condition and having removed all temporary structures, equipment, plant and materials.

WI 404 Security

1. All existing landowner security arrangements shall be reinstated upon completion unless agreed otherwise. The *Contractor* shall ensure that landowner security is maintained at a similar level to that which currently exists on the site during the implementation of the works.

WI 405 Pre-Completion arrangements

- 1. Prior to any works being offered for takeover or Completion the *Contractor* shall arrange a joint inspection with the *Supervisor*, *Project Manager* and the *Employer*.
- 2. The initial inspection shall take place a minimum of three weeks in advance of the planned Completion.

WI 500 Programme

WI 501 Programme Requirements

 The Contractor shall programme the revetment construction works to make best use of tidal working periods so as to minimise the exposure of underlayers to unfavourable sea conditions.

WI 502 Revised Programmes

1. Submission of revised programmes shall be accompanied with a written explanation of the changes.

WI 600 Quality Assurance

WI 601 Samples

1. Concrete cube samples shall be required to verify the strength of the concrete. The procedure shall be in line with the minimum technical standards (4.9).

WI 602 Quality Statement

1. The *Contractor* shall submit his quality statement for the works to the *Project Manager* within 4 weeks of the starting date.

WI 603 Quality management system

 The Contractor's quality management system shall comply with the requirements of ISO 9001 and ISO 14001.

WI 700 Tests and inspections

- 1. At the commencement of the armour stone placement, the *Contractor* shall be required by the *Supervisor* to construct a test section of the structure which shall be used to demonstrate the quality of placing of armour stone for all layers, for approval by the *Supervisor*. See Appendix B, section 4.3 for further details.
- 2. No revetment layer shall be covered by a subsequent layer until the profile of the former layer has been approved by the *Supervisor*. See Appendix B, section 4.5 for further details.
- 3. Upon completion of the works the *Contractor* will undertake a level survey of the revetment for acceptance by the *Supervisor*. See Appendix B, section 4.8 for further details.
- 4. The *Contractor* shall keep daily photographic records of all works carries out. All structures, pipework, formation levels, construction materials etc buried shall be photographed prior and during burying operations.

WI 800 Management of the works

WI 801 Project team - Others

1. Refer to Contract Data for details.

WI 802 Communications

1. No additional requirements to those stated in the MTR

WI 900 Working with the Employer and Others

WI 901 Sharing the Working Areas with the Employer and Others

- 1. The *Contractor* is required to co-operate with Others in sharing the working areas they need in connection with the works.
- Statutory bodies (the local planning authority, MMO, Natural England etc.) may arrive at site
 unannounced to assess whether the works are being implemented within the conditions of
 the granted consent. The Contractor shall co-operate with any reasonable requests and
 share the working area.

WI 1000 Services and other things to be provided

WI 1001 Services and other things for the use of the *Employer, Project Manager* or *Others*

- The details of services and other things for the use of the Employer, Project Manager or Others to be provided by the Contractor are listed in the Environment Agency Minimum Technical Requirements (1.2)
- 2. The Contractor is responsible for obtaining all temporary service connections required for the duration of the works, including power, water, gas and telecommunications. Where no fixed connection is to be used, the Contractor is responsible for making alternative arrangements. In the case of sewerage for instance, the Contractor is responsible for safely disposing of any waste generated if no connection to a public sewer is available.

WI 1002 Services and other things to be provided by the Employer

- 1. The *Employer* is responsible for the following: -
 - Obtaining permission from the landowner to use the site for the purposes of the works.
 The Contractor should not approach any landowner directly unless authorised to do so by the Employer.
 - Obtaining Marine Management Organisation consent for the works.
 - Giving the *Contractor* access to the site. The *Contractor* must give 5 working days' notice to the *Employer* to gain access to the site during the defects correction period.

WI 1100 Health and safety

WI 1101 Health and safety requirements

- 1. The *Contractor* shall comply with all applicable legislation for the health, safety and welfare of his people or any other person in or near the Site of the *works*.
- 2. The *Contractor* copies to the *Project Manager* into all correspondence with the *Principal Designer*.
- 3. The *Contractor* shall fulfil the role of Principal Contractor under the Construction Design and Management Regulations 2015 for the duration of the works.

Toolbox talks

1. The *Contractor* provides regular toolbox talks to site personnel to ensure that health and safety issues, the requirements of the contract and the design and the contents of method statements are communicated throughout the site team.

Incident reporting

1. The *Contractor* shall provide a written report within 21 days of the incident, unless otherwise agreed with the *Project Manager*.

First Aid

 The Contractor shall provide first aid facilities; Materials and personnel trained in first aid, for the benefit of his own people, those of his Subcontractors and the site staff of the Project Manager, Supervisor and Employer.

Provision of Life Saving Equipment

1. The majority of the works will be undertaken immediately adjacent to water. Lifesaving equipment will be provided to the satisfaction of the *Project Manager*.

WI 1102 Method statements

- 1. The *Contractor* shall submit Method Statements to the *Project Manager* at least two weeks in advance of carrying out items of work including proposed method of forming the revetment profiles indicated on the drawings.
- 2. The Contractor shall not commence any permanent works until the *Project Manager* has approved in writing the *Contractor's* working methods for forming the works.
- 3. The Contractor provides the works in accordance with the accepted method statement.

WI 1103 Legal requirements

- 1. The Principal Contractor duties under the CDM Regulations 2015 shall be undertaken by the *Contractor*.
- 2. The Principal Designer duties under the CDM Regulations 2015 shall be undertaken by the *Employer's* consultant- Arcadis.
- 3. The Client duties under the CDM Regulations 2015 shall be undertaken by the Employer.

WI 1104 Inspections

1. The *Contractor* shall provide a competent health and safety officer whilst *works* are being carried out on the Site.

- 2. The *Contractor's* health and safety officer carries out weekly audits of the Site and submits copies of audit reports and proposed remedial actions to the *Supervisor* prior to the end of the following week.
- 3. The *Employer* may carry out site audits. The *Contractor* assists in these audits and complies with any recommendations made during such audits.

WI 1200 Subcontracting

1. The *Contractor* is responsible for all the work.

WI 1300 Title

1. Not required.

WI 1400 Acceptance or procurement produce (Option C, D, E and F)

1. Not required.

WI 1500 Accounts and records (Options C, D, E & F)

1. Not required.

WI 1600 Parent company guarantee (Option X4)

1. Not required.

WI 1700 Performance Bond (Option X13)

1. Not required.

WI 1800 Advance payment bond (Option X14)

1. Not required.

WI 1900 Low Performance damages (Option X17)

1. Not required.

WI 2000 Employer's work specifications and drawings.

WI 2100 Employer's work specification

- The Employer's minimum technical requirements are the Civil Engineering Specification for the Water Industry (CESWI), 7th Edition, supplemented by the Environment Agency's Minimum Technical Requirements (EA MTR). See Appendix A.
- 2. The Specification for Highway Works (SHW) standards are applicable where it is referenced in the Works Information.
- 3. The General Specification for the rock revetment is The Rock Manual The Use of Rock in Hydraulic Engineering 2nd Edition (CIRIA C683) 2007. This is supplemented by additional clauses contained within the Particular Rock Revetment Specification. See Appendix B.
- 4. In so far as any information contained within the Works Information (including the Works Specification) may conflict or be inconsistent with any provision of CESWI 7 and/or the EA MTR then the particular information contained within the Works Information shall always prevail.
- 5. CEWSI & EA MTR clauses should be read as those clauses which are applicable to works apply and those that are not relevant should be ignored. E.g. Clause 2.102: Precast Concrete Box Culverts is not applicable as it is not shown on the drawings and not mentioned in the Works Information. Therefore, text relating to those clauses in CEWSI & EA MTR should be ignored. However, if the design is modified during construction to include works for such an item, the clause should be adhered to.
- 6. The following reports and specifications form a part of the Works Information:
 - Appendix A Employer's Minimum Technical Requirements- (EA MTR)
 - Appendix B Rock Revetment Specification

N.B. It is assumed the *Contractor* will have access to CESWI 7 and other industry standard references made within the Works Information and hence will not be distributed as part of the Contract Documents.

WI 2200 Drawings

- 1. The following drawings form a part of the Works Information:
 - UA008878-ARC-XX-XX-DR-CE-0200-P1-PorthlooSitePlan
 - UA008878-ARC-XX-XX-DR-CE-0220-P4-PorthlooRevetmentPlan
 - UA008878-ARC-XX-XX-DR-CE-0221-P5-PorthlooSectionSheet1
 - UA008878-ARC-XX-XX-DR-CE-0222-P5-PorthlooSectionsSheet2
 - UA008878-ARC-XX-XX-DR-CE-0223-P4-PorthlooSectionsSheet3
 - UA008878-ARC-XX-XX-DR-CE-0230-P1-PorthlooRetainingWallGA
 - UA008878-ARC-XX-XX-DR-CE-0231-P1-PortLooRetainingWallRC

APPENDIX A

EMPLOYER'S MINIMUM TECHNICAL REQUIREMENTS-EA MTR



APPENDIX B ROCK REVETMENT SPECIFICATION

