

RECEIVED

By Liv Rickman at 2:33 pm, Aug 04, 2023

Site Waste Management Plan –

MATERIAL IN

- Slate transported on wood pallets with steel straps.
- Timber Transported in bundles with steel Straps
- Roof Membrane on wood pallets
- Lead & Fixings on wood pallets

Material sourced from Builders Merchants Penzance Cornwall
Transport Steamship Company Island Carriers

WASTE MATERIAL

Slate transported to crushing plant at MacFarland Down for use on local tracks & Paths (The existing slate is in poor condition however there maybe a few that are suitable for reuse by local trades)
Timber in good condition will be offered to local trades, or for firewood, any surplus will be transported to the council depot for pulping. Wood pallets to be returned to the builders Merchants, Damaged Pallets or nonreturnable to be offered to local people or sent for pulping
Lead, Steel straps, fixings etc , transported to council depot for recycling. (The old lead may be suitable for reuse by other trades depending on condition)

COMMENT

There may well be plastic waste depending on the packaging different company's use i.e. shrink wrap etc .however I expect the waste to exceed 90% recycle or reuse