

Tree Surgery & Arboricultural Consultancy 01803 814126 www.devontreeservices.co.uk info@devontreeservices.co.uk

Arboricultural Appraisal DTS22.2103.1.AA Accompanied by Tree Appraisal Plan DTS22.2103.1.TAP

Site: Carn Thomas, Isles of Scilly

Report date: 20th October Client: Kirkham Board Author: Simon Putt





All rights in this report are reserved. No part of it may be reproduced or transmitted, in any form or by any means, electronic, mechanical, photocopying, recording or otherwise, or stored in any retrieval system of any nature, without our written permission. Its content and format are for the exclusive use of the addressee in dealing with this site. It may not be sold, lent, hired out or divulged to any third party not directly involved in this site without our written consent. 2019 © Devon Tree Services Ltd

1 Scope, methodology & limitations

- 1.1 The appraisal is an overview of tree quality on site and is designed to provide general guidance on how layout design and trees can work together. The tree survey method makes reference to BS5837:2012 (Trees in relation to design, demolition and construction Recommendations).
- 1.2 Assessment of the potential influence of trees upon buildings or other structures resulting from interaction with shrinkable soils is excluded and soil type is not assessed. All dimensions including the crown spread and tree heights have been estimated.
- 1.3 Please bear in mind that the condition of trees can change following severe weather conditions, the effects of diseases or pests, and other abiotic factors so the accuracy of this report decreases as time passes. This report is valid for 12 months from the date of site inspection. No trees have been tagged.

2 Overview

- 16 arboricultural features were inspected on the 20th October 2022 from ground level.
- The trees on site are mainly scrub broadleaves growing in amongst bramble and low growing vine.
- According to BS5837 categorisation, there are 0 'A' quality features, 0 'B', 16 'C' and 0 'U'.

2.1 Root protection area (RPA)

The RPA for the trees are listed in the tree survey schedule **22.2103.1.SCH**, and illustrated on drawing **22.2103.1.TAP**. Using stem diameter measurements, this is the default area where roots should be protected however the shape and size may be altered if ground conditions dictate.

3 General considerations for design

- 3.1 To accommodate the retained trees and reduce planning issues, I recommend considering the following:
- 3.2 <u>Construction process:</u> Provide sufficient space for the construction process. The position of contractor car parking, storage of materials, and provision of adequate working space should fall outside the RPA where possible.

3.3 <u>Dwellings and trees (refer to tree appraisal plan for guidance):</u>

- Orientate plots so tree canopies are well away from dwellings allow at least 5 metres between the canopy tip and dwelling for mature trees.
- If large veteran trees or large tree groups are retained, consider making them part

Page 2 of 6

Report author: Simon Putt Client: «Client»
Report date: 20th October

- of open space and try to avoid including them into gardens of dwellings
- Services and drainage: The default position is to avoid installing services within the 3.4 RPA of trees. If this is not viable, it may be possible to use special trenching techniques but they can be more complicated and may need the use of an air spade.
- 3.5 Construction damage: To retain the trees, trenching type excavations within the root protection area should be avoided, however it may be possible subject to further ground investigations using an air spade. It is sometimes possible to build light structures and narrow minor roads or drives subject to using suitable construction detail and methodology.
- 3.6 Construction access: Access for construction traffic ideally should avoid the RPA and canopy of all trees; this avoids the need for extensive tree protection measures. If unavoidable, tree pruning may be needed and temporary ground protection measures will need to be installed.
- 3.7 **<u>Tree planting:</u>** Trees benefit new development in many ways and new planting areas sometimes need protecting as existing trees.

Tree quality 4

Tree retention, removal and replacement:

- In terms of planning, it is generally favourable to retain as many 'A' and 'B' quality 4.1 trees as possible, however it is also important to avoid problems between new structures and existing trees, for example, new dwellings being too close to tree canopies.
- 4.2 When tree removals are needed, 'U' (red) trees are not safe to retain in a development and can be justifiably removed on arboricultural grounds alone.
- 4.3 It is fair to assume that 'C' (grey) quality trees can be removed to facilitate development, however some mitigation tree planting is generally recommended depending on the number of 'C' tree removed.
- 4.4 Wherever possible, 'B' (blue) quality trees should ideally be retained as they are often prominent or large trees. However, sometimes development will not be possible without their removal but this should be kept to a minimum and welldesigned new tree planting carried out.
- 4.5 The most important trees are 'A' (green) quality and they should be retained unless there are no other viable options. Where 'A' trees are proposed for removal there needs to be good justification in terms of the layout design constraints and more substantial mitigation tree planting would form part of the new development.

Report author: Simon Putt Client: «Client»

Report date: 20th October

5 General constraints

- 5.1 **Tree protection**: these trees may be protected by a tree preservation order, so it might be necessary to obtain consent from the Local Planning Authority (LPA) before any pruning works other than certain exceptions can be carried out.
- 5.2 **Crown spread:** the crown spread is a general indication of current branch length taken at the four cardinal points. Details of the lowest branch and its direction can be found within the Tree Survey Schedules. It is recommended to allow 5 metres between the canopy tip and dwelling for mature trees as a minimum. If large tree groups are retained, consider making them part of open space and try to avoid including them into gardens of dwellings.
- 5.3 **Root protections areas (RPAs):** the RPA represents the below-ground constraints posed by trees and are determined in line with recommendations set out in section 4.6 of BS 5837:2012. Design within this area should be avoided.
- 5.4 The RPA is initially plotted as a circle centred on the base of the stem. However, where the arboriculturist believes that pre-existing site conditions or other factors influence the RPA, modifications to the shape can be undertaken.
- 5.5 The default position is that structures and services are located outside of the RPAs of trees which will be retained.
- 5.6 **Shade area**: shading of buildings by trees can be or can become an issue where there are rooms that require natural light. Proposed buildings should be designed to take account of existing trees and the shade that they cast.
- 5.7 The area is plotted as a segment with a radius from the centre of the stem equal to the height of the tree and is drawn from due north-west to due east. This indicates the shadow pattern through the main part of the day.

6 Tree planting

- 6.1 Species selection, planting location, tree size, future size potential, and establishment and maintenance requirements (watering etc) should all be considered during the layout design process under the guidance of an arboricultural consultant.
- 6.2 Planting in soft open landscaped areas like amenity space or playing fields is reasonably simple to implement provided the above conditions are suitably addressed.
- 6.3 Planting where hard surfaces surround trees (for example in a car park or a narrow shrub bed abounded by a driveway) is more complex as design needs to consider how trees receive sufficient nutrients, air and water to survive and grow to maturity. This is a specialist form of tree planting and should be designed with arboricultural advice.

Simon Putt | MArborA, Cert Arb L6 (ABC), Tech Cert (ArborA) Director and Consultant Arboriculturist

Report author: Simon Putt Client: «Client»

Report date: 20th October

Devon Tree Services «KF_Job_Number».1.AA

Cascade chart for tree quality assessment (extract from BS5837:2012 Trees in relation to design, demolition and construction Recommendations)


Category and definition	Criteria (including subcategories where a	appropriate)		Identification on plan
Trees unsuitable for retention (see Note)				-
Category U	 Trees that have a serious, irremediable, structural defect, such that their early loss is expected due to collapse, including those that will become unviable after removal of other U category trees (i.e. where, for whatever 			
Those in such a condition	reason, the loss of companion shelter cannot be mitigated by pruning)			
that they cannot realistically	 Trees that are dead or are showing signs of significant, immediate, and irreversible overall decline. 			
be retained as living trees in	 Trees infected with pathogens of significance to the health and/or safety of other trees nearby, or very low 			DARK RED
the context of the current	quality trees suppressing adja			
land use for longer than	NOTE Category U trees can have existing or potential conservation value which it might be desirable to preserve;			
10 years	see 4.5.7 .			
	1 Mainly Arboricultural values	2 Mainly landscape values	3 Mainly cultural values, including conservation	
rees to be considered for retention				
Category A	Trees that are particularly good examples of their species, especially	Trees, groups or woodlands of particular visual importance as arboricultural and/or	Trees, groups or woodlands of significant conservation, historical,	
Those of high quality and value: such a	if rare or unusual, or essential	landscape features	commemorative or other value (e.g.	LIGHT GREEN
condition as to be able to make a substantial	components of groups, or of formal	•	veteran trees or wood-pasture)	
contribution (a minimum of 40 years is	or semi-formal arboricultural features			
suggested)	(e.g. the dominant and/or principal			
	trees within an avenue)			
Category B	Trees that might be included in	Trees present in numbers, usually growing	Trees with material	
Those of moderate quality and value: those	category A, but are downgraded	as groups or woodlands, such that they	conservation or other	MID BLUE
in such a condition as to make a significant	because of impaired condition (e.g.	attract a higher collective rating than they	cultural value	MID PLUE
contribution (a minimum of 20 years is	presence of significant though	might as individuals; or trees occurring as		
suggested	remediable defects, including	collectives but situated so as to make little		
	unsympathetic past management and	visual contribution to the wider locality		
	storm damage), such that they are			
	unlikely to be suitable for retention for			
	beyond 40 years; or trees lacking the			
	special quality necessary to merit the			
	category A designation		-	
Category C	Unremarkable trees of very limited	Trees present in groups or woodlands, but	Trees with no material conservation	
Trees of low quality with an estimated	merit or such impaired condition that	without this conferring on them	or other cultural value	ODEV
remaining life expectancy of at least 10	they do not qualify in higher	significantly greater collective landscape		GREY
years, or young trees with a stem diameter below 150 mm	categories	value; and/or trees offering low or only		
DEIOW 150 IIIIII		temporary/transient landscape benefits		

Report author: Simon Putt

Client: «Client»

Report date: 20th October

PHOTOGRAPHS











Page 6 of 6